

## Preliminary

- QBCC Building insurance fee
- Soil test sites < 15% slope
- Site detail /contour survey
- Wind classification report
- Effluent report (site dependant additional fee \$1100)
- Energy efficiency report
- Bushfire report (site dependant additional fee \$1520)
- Flood report (site dependant additional fee \$140)
- Engineering design
- Building approval fees and lodgement
- Temporary fencing to site (site dependent)
- Earthworks up to combined 500mm cut/fill for level pad
- Setout survey
- Connections 10m allowed for water, sewer, electricity and stormwater
- Telephone/NBN Site specific (additional fee price site dependent)
- Selections and interior/exterior design meeting

## Structural

- Termite resistant timber frame and roof trusses to N3 Wind classification
- Flickguard termite barrier with 50 year warranty
- Concrete slab 'M' slab no allowances for piering or retaining walls
- Building construction to Bal LOW

## Energy Efficiency

- 55mm Foil backed insulation blanket under roof sheet
- Minimum R2.5 insulation to internal living ceiling areas (patios/verandahs excluded)
- Wall wrap sisalation to external walls
- R2.0 wall insulation to external walls (carport walls excluded)
- Ceiling fan to outdoor living
- Minimum 3-star WELS rating for shower heads and 4-star WELS rating for tapware and toilets
- Weather seals to aluminium windows Draft seals to external hinged doors including front entry door



- Roof Standard Colorbond roofing, gutter and fascia. Trimdeck profile.
- 90mm round PVC painted downpipes
- 600mm eaves

Standard Colorbond colours

TRIMDECK PROFILE

 Claddings – As per plan locations – Scyon Axon 133, JH Fine Texture 1200, BGC Duragrid, NewTechwood

FINE TEXTURE

AXON

DURAGRID

NEWTECHWOOD

- Dowell Windows/sliding doors 2100mm high head height. Standard clear glass, obscure to bathroom.
- Powder coated aluminium framed windows and sliding doors Standard flyscreens Flymesh to openable windows and glass sliding doors Entry door excluded)

Optional upgrades – Crimmesh screens \$ 4555

## Exterior (Continued)

- External ceilings 6mm F.C lining with PVC joints

  \*\*Optional upgrade Verandah ceilings (excluding carport and patio) 9mm Fijian Cedar Ply lined with timber batten joins -\$535

  \*\*Eaves 4.5mm F.C lining\*\*
- Verandah posts 90x90mm Merbau
   Optional upgrade Added 70x45 Merbau post screen to enclose carport rear \$2560
- External floors Plain concrete

  Optional upgrade Tiling 450x450 exterior tiles Choice of Builder's Range \$3770 Patio & Verandahs only. Carport plain concrete



Entry handle / lock — Gainsborough Trilock Contemporary Align Colours Chrome or Satin Chrome HUME SAVOY 820 RANGE

TRILOCK ENTRY DOOR HANDLE







Door handles – Swing doors - Gainsborough Choice series passage/privacy
 Colours Satin chrome and Bright chrome.

GAINSBOROUGH CHOICE SERIES



- Cavity sliding doors Gainsborough Circular sliding passage/ privacy
  - Colours Satin chrome and Bright chrome

- Gainsborough door stops
  - Colours Satin chrome and bright chrome

Architrave and skirting boards
 42x11 LOSP FJ pine architraving – Standard profile range

BULLNOSE SINGLE BEVEL PENCIL ROUND COOLUM COVE HALF SPLAYED













67x11 LOSP FJ pine skirting boards – Standard profile range
















- Oven
   Baumatic 60cm Electric Oven BO5M 60cm Multifunction oven
- Cooktop Baumatic 60cm Ceramic Cooktop BCT4 60cm ceramic glass

  Ontional ungranda Baumatic Industries and Industries Cooktop BCT4 60cm ceramic glass







In your preliminary stage, a selections meeting appointment will be made to choose your final fittings and colour choices for your home with one of our expert team members. We take the time to understand your needs and our experts will be there to help you through the process. This can be done in two convenient locations — National Tiles Design Studio Warana or our office in Corbould Park Qld.

Note: Price includes standard inclusions for sewered site with slab on ground construction <15% slope. Sloping sites >15% slope with off ground construction will incur additional costs. Price site dependent.

Windows, screens, external door and external building elements subject to site energy efficiency and bushfire reports. Additional costs will be incurred if report results to subject site are above standard inclusions.

Non sewered sites – Water tank and treatment plants not included. Can be included at additional cost. Price site dependent.

No NBN or telephone points included. Can be included at additional cost. Price site dependent.